

6 July 2023

Our Ref: 4806188 File Ref: OPW2023/0002 Enquiries: Jorja Feldt

RJG Builders C/- Milford Planning PO Box 5463 **TOWNSVILLE QLD 4810**

Sent via email: info@milfordplanning.com.au

Dear Paul,

Decision Notice – Approval

(Given under Section 63 of the Planning Act 2016)

The assessment manager wishes to advise that the application was approved under delegated authority on 6 July 2023. The approval is subject to reasonable and relevant conditions and supported by a notice of reasons as detailed below:

Applicant details **RJG Builders C/- Milford Planning** Applicant name: Location details 9 Burdekin Street, Richmond Hill QLD 4820 Street address: Real property description: Lot 1 on MPH199999 Current lawful use: Community use - Scouts building Application details Application number: OPW2023/0002 Approval type: **Development Permit** Development type: **Operational Work** Category of assessment: Code Assessment Description of development: Earthworks (excavation and filing) and Stormwater Management Infrastructure associated with MCU2023/0003 Charters Towers Regional Town Plan Version 2 Categorising instrument: 1. Details of the approval

Details of the approval are listed below in accordance with the Planning Regulation 2017.

PO Box 189 Charters Towers Qld 4820 ADMINISTRATION: 12 Mosman Street Charters Towers Qld 4820 Australia PH. (07) 4761 5300 | F. (07) 4761 5344 | E. mail@charterstowers.qld.gov.au | ABN. 67 731 313 583 www.charterstowers.qld.gov.au





Date: 6 July 2023

	Our R	lef: 4806188	
	Planning Regulation 2017 reference	Development Permit	Preliminary Approval
Development assessable under the planning scheme, a temporary local planning instrument, a master plan or a preliminary approval which includes a variation approval		\boxtimes	

2. Conditions of approval

Condition Number	Condition					Timing
Approved P 1)	submitted app	is to be carri lication inclu n except whe	iding the fol ere amendri	erally in accordance w lowing plans and sup nents are required to s	porting	At all times
	Drawing Title:	Prepared by:	Date:	Reference No:	Revision:	
	Civil Works Layout Plan	Northern Consulting Engineers	31.3.2023	CBD0072/01	P2	
	Earthworks Layout Plan	Northern Consulting Engineers	31.3.2023	CBD0072/02	P2	
	Structural Layout Plan	Northern Consulting Engineers	31.3.2023	CBD0072/03	P2	
	Construction Details	Northern Consulting Engineers	31.3.2023	CBD0072/04	P2	
	Site Based Stormwater Management Plant	Northern Consulting Engineers	31.3.2023	CBD0072/SBSM01	P1	
2)	and a digital c and accepted	opy in PDF f by Council. Engineer Que	ormat corre	roposed works (one p ctly scaled), must be are to be certified by PEQ) and to be acco	re-submitted a Registered	Prior to commencement of construction
3)	As constructed acceptance pr maintenance'.	d informatior ior to inspec The data is application re	tions or plactions or plactions or plaction to be submised and the submised of	ubmitted to Council fo cing the construction itted with a cover note gal description of the tails.	'on e detailing the	Prior to commencement of construction
General					14	A 11 4:-
4)				is Development Perm s) and document(s) in		At all times

ADMINISTRATION: 12 Mosman Street Charters Towers Qld 4820 Australia

PH. (07) 4761 5300 | F. (07) 4761 5344 | E. mail@charterstowers.qld.gov.au | ABN. 67 731 313 583 www.charterstowers.qld.gov.au





Date: 6 July 2023

	Our Ref: 480618	8
Condition Number	Condition	Timing
	 b) Meet the cost of all works associated with the development including any alterations, relocations or repairs to damaged Council infrastructure, and a) All repairs, alterations and relocations of Council infrastructure are to be in accordance with the relevant Council policy and/or Australian Standard. 	
Environme	ital	
5)	Ensure that erosion and sedimentation control management is undertaken and maintained to prevent soil erosion and sedimentation runoff to watercourses and Council's storm water drainage system. Erosion and sediment control is to be in accordance with <i>International Erosion Control</i> <i>Association – Best Practice Erosion & Sediment Control guidelines</i> and the <i>Queensland Urban Drainage Manual 2017.</i>	As part of construction and thereafter
6)	The construction of the development (not operation) must be limited to 0630—1830 Monday to Saturday and not at all on Sunday and public holidays as per Section 440R of the <i>Environmental Protection Act 1994</i> . Noise generated from construction must be within the limits set by the <i>Environmental Protection Act 1994</i> and the <i>Environmental Protection</i> (Noise) Policy 20019.	At all times
7)	 Ensure that: a) Works occur so they do not cause unreasonable interference with the amenity of adjoining premises because of noise, air or other chemical pollutants b) The premises including the adjoining Council controlled road reserve are kept in a safe, clean and tidy state, and c) All construction materials are contained wholly within the premises. 	As part of construction
8)	 Do not place earth fill adjacent or in proximity to any site boundary unless: a) The fill is retained on the boundary with approval from Council, and b) Adjoining properties are not adversely affected with respect to a loss of privacy and safety (caused by the ability for example to look over boundary fences) and changes in the natural drainage pattern because of the works. 	As part of construction
Stormwater		
9)	Applicant to construct discharge to kerb as approved in the development approval and without causing or resulting in nuisance at the discharge location. In the event discharge is found to cause nuisance in the future, the applicant must re-engineer the discharge and remedy it to the satisfaction of Council and at no cost to Council.	At all times.
Pre-constru		
10)	 Contact Council to arrange a pre-start meeting. The pre-start meeting must include the following: a) Notification of the principal contractor for the works b) A copy of the contractor's public liability insurance policy for a minimum of twenty million dollars indemnifying Council against all claims resulting from the construction works of this development 	Prior to commencement of construction





Date: 6 July 2023 Our Ref: 4806188

	Our Ref: 4806188	
Condition Number	Condition	Timing
	c) A programme of works, demonstrating all major activities and milestones, and	
	d) A Traffic Management Plan addressing the following:	
	 safe and accessible pedestrian movement in and around the site over the life of the project: 	
	 ii) access and egress for the site over the life of the project iii) haul routes for earthworks and other construction activities over the life of the project iv) general traffic guidance around the site over the life of the project, 	
	and v) proposed parking areas for construction vehicles, staff working on-	
Maintenand	site and visitors.	
11)	A maintenance and defects bond calculated at 5% of the total cost of construction for all works which are to be transferred to Council upon the completion of the development is to be paid. The costs of the construction are to be demonstrated be an itemised bill of quantities provided by a RPEQ. The bond is to be held by Council in trust until the works are considered 'off maintenance'.	Prior to works being requested to be 'on maintenance'
12)	An 'on maintenance' inspection is required to be undertaken and the works which are to be transferred to Council must be placed 'on maintenance' for a minimum period of twelve months (maintenance period) following the satisfactory demonstration and inspection of the final works.	After completion of construction
13)	Upon the completion of the 'maintenance period', rectification of all defects identified by Council are to be completed to the satisfaction of Council. Upon Council being satisfied with the results of an 'off maintenance' inspection and compliance against development approvals conducted by council Officers following the end of the maintenance period.	After completion of maintenance period
Transport a		
14)	Lodge and obtain approval for an application to carry out public access/footpath work as part of works within the Council controlled road reserve.	Prior to works within Council's road reserve
15)	All pedestrian footpaths are to be constructed in accordance with Council's standard drawing <i>CTRC-006 Roads cross section footpath types with joining and Telstra joining details</i> .	As part of construction
16)	All driveway crossovers are to be constructed accordance with Council's standard drawing CTRC-003 Roads commercial driveway slab.	As part of construction
17)	Car parking spaces are to be constructed on site generally in accordance with the approved plans, including designated disabled car parking spaces. These spaces and all vehicle movement areas are to be constructed, sealed, line marked, provided with wheel stops and maintained in accordance with and AS2890.1 Off-Street Car Parking and the Manual of Design Vehicles and Turning Path Templates SAA HB 72 (AUSTROADS 1995).	As part of construction

ADMINISTRATION: 12 Mosman Street Charters Towers Qld 4820 Australia

PH. (07) 4761 5300 | F. (07) 4761 5344 | E. mail@charterstowers.qld.gov.au | ABN. 67 731 313 583 www.charterstowers.qld.gov.au



Date: 6 July 2023

Condition Number	Condition	Timing
18)	Under Part 1 Clause 1.10 of the Manual of Uniform Traffic Control Devices Queensland, Council delegates the principal contractor the responsibility for the installation of all official traffic signs installed in accordance with the methods, standards and procedures prescribed in the Manual of Uniform Traffic Control Devices, or other duly approved documents.	As part of construction
19)	The design and installation of all street, path or public lighting in accordance with <i>AS/NZ 1158 Lighting for roads and public spaces</i> must be be at no cost to Council. The street and path light system must be designed in accordance with the <i>'Crime Prevention through Environmental</i> <i>Design: Guidelines for Queensland'</i> produced by the Queensland Government and unless otherwise approved by Council in writing, be powered using underground power.	As part of construction
Earthworks		
20) Retaining V	 All site and earthworks must: a) Be undertaken in accordance with <i>AS/NZ</i> 3798 Guidelines on Earthworks for Commercial and Residential Developments b) Be in accordance with Australian Standard 1289 Methods of Testing Soils for Engineering Purposes, c) Comprise of clean fill and be compacted to building pad standard. A Supervision certificate by a Registered Professional Engineer of Queensland must be submitted to Council upon completion of works, and d) Ensure compliance with Part 3B of the Environmental Protection Act 1994, which prohibits unlawful environmental nuisance caused by dust, beyond the boundaries of the property. 	As part of construction
21)	All retaining walls must be designed in accordance with AS/NS 4678 Earth- retaining structures. Retaining walls must not impose loads on underground services, within allotments or external to allotments. The design and construction of retaining walls must be certified by a RPEQ experienced in this type of work.	As part of construction

Advisory Notes

 Aboriginal and Cultural Heritage
 A. The Aboriginal Cultural Heritage Act 2003 and Torres Strait Islander Cultural Heritage Act 2003 requires anyone who carries out a land-use activity to exercise a duty of care. Land users must take all reasonable and practicable measures to ensure their activity does not harm Aboriginal or Torres Strait Islander cultural heritage. Prior to carrying out works, it is advised that you contact the Department of Aboriginal and Torres Strait Islander Partnerships on (07) 4799 7470 or by post at PO Box 5620 TOWNSVILLE QLD 4810. For further information on cultural heritage duty of care please visit: https://www.datsip.qld.gov.au/people-communities/aboriginal-torres-strait-islander-culturalheritage/cultural-heritage-duty-care
 Abandoned Mine Shafts
 B. The city of Charters Towers is subject to a significant number of abandoned mine shafts due to the former gold rush era. It is recommended that all searches be undertaken through the Queensland State





Date: 6 July 2023 Our Ref: 4806188

	Oul Rel: 4000100
Ad	visory Notes
	Government's Department of Natural Resources Mines and Energy (DNRME) to ensure that the
	development is not unduly impacted upon by these shafts. The DNRME can be contacted on 13 74 68.
Wo	orkplace Health and Safety
C.	Ensure compliance with the <i>Work Health and Safety Act 2011</i> . It states that the project manager is obliged to ensure construction work is planned and managed in a way that prevents or minimises risks to the health and safety of members of the public at or near the workplace during construction work. It is the principal contractor's responsibility to ensure compliance with the <i>Work Health and Safety Act 2011</i> . It states that the principal contractor is obliged on a construction workplace to ensure that work activities at the workplace prevent or minimise risks to the health and safety of the public at or near the workplace to ensure the workplace during the work. It is the responsibility of the person in control of the workplace to ensure compliance with the <i>Work Health and Safety Act 2011</i> . It states that the person in control of the workplace is obliged to ensure there is appropriate, safe access to and from the workplace for persons other than the person's workers.
En	vironmental nuisance
D.	Ensure compliance with the <i>Environmental Protection Act 1994</i> . It states that a person must not carry out any activity that causes, or is likely to cause, environmental harm unless the person takes all reasonable and practicable measures to prevent or minimise the harm. Environmental harm includes environmental nuisance. In this regard persons and entities, involved in the civil, earthworks and construction phases of this development, are to adhere to their "general environmental duty" to minimise the risk of causing environmental harm.
	Environmental harm is defined by the Act as any adverse effect, or potential adverse effect whether temporary or permanent and of whatever magnitude, duration or frequency on an environmental value and includes environmental nuisance. Therefore, no person should cause any interference with the environment or amenity of the area because of the emission of noise, vibration, smell, fumes, smoke, vapour, steam, soot, ash, dust, waste water, waste products, grit, sediment, oil or otherwise, or cause hazards likely in the opinion of the Council to cause undue disturbance or annoyance to persons or affect property not connected with the use.
Air	port Operations
E.	Where works may impact on the safety operation of the Charters Towers Airport such as the use of cranes, industrial lighting or involve impacts such as gaseous plumes, it is advised that you contact one of Council's Airport Reporting Officer(s) on (07) 4761 5300 prior to works commencing.
Erg	gon Energy and Telstra Corporation Contact Details
F.	 Where a condition requires connections to reticulated electricity and/or telecommunications or a certificate of supply, please contact the below: a) Ergon Energy Connection Solution's Team – (07) 4931 1012, and/or b) NBN Co – 1800 687 626.
_	uncil Forms, Policies and Drawings
G.	 In achieving compliance with conditions, the below Council forms may need to be completed for this development: a) F0227 - Application to carry out works on a Council road (including pathways) b) Standard drawings and specifications for driveways and roads c) F0313 - Request for water supply connection or disconnection d) F0347 - Application for sewer main cut-in





Date: 6 July 2023 Our Ref: 4806188

3. Currency period for the development application approval

In accordance with section 85 of the *Planning Act 2016*, this approval has a currency period of two years.

4. Further development permits

Not applicable.

5. Referral agencies

Not applicable.

6. Submission(s)

Not applicable.

7. Other requirements under section 43 of the Planning Regulation 2017

There are no other requirements.

8. Appeal rights

The rights of an applicant to appeal to a tribunal or the Planning and Environment Court against a decision are set out in Chapter 6, Part 1 of the *Planning Act 2016*. For particular applications, there may also be a right to make an application for a declaration by a tribunal (see Chapter 6, Part 2 of the *Planning Act 2016*). Information about how to proceed with an appeal to the Planning and Environment Court may be found on the Court's website: http://www.courts.qld.gov.au/courts/planning-and-environment-court.

An applicant may also have a right to appeal to the Development tribunal. For more information, see schedule 1 of the *Planning Act 2016*. The timeframes for starting an appeal in the Planning and Environment Court are set out in Section 229 and Schedule 1 of the *Planning Act 2016*.

Should you wish to discuss this matter, please contact Jorja Feldt, Planner on (07) 4761 5300.


Yours faithfully

Hayley Thompson Executive Manager Community Building

Enc. Approved Plans

PO Box 189 Charters Towers Qld 4820 ADMINISTRATION: 12 Mosman Street Charters Towers Qld 4820 Australia PH. (07) 4761 5300 | F. (07) 4761 5344 | E. mail@charterstowers.qld.gov.au | ABN. 67 731 313 583 www.charterstowers.qld.gov.au







pit	to	
Dipe		
o wn		
Re		
ке	rer.	

pit		
oipe	2	
wn		
Re	fer	


.250fs	 Finished surface level
00.300	– Pipe invert level.
	– Stormwater overland
03.50	– Design major contour.
03.10	– Design minor contour.
\cdots	- Drainage path Invert.






	-303.50
	-303.10
	-303.50
	-303.10
	·····
(S)	(S)







drawi	ngs & site.	
- ISSUED FOR APPROVAL. - ISSUED FOR INFORMATION.		31/03/2023 6/03/2023
Description		Date
DEVELOPMENTS	STRUCTURAL LAYOUT PLA	N
VELOPMENT EKIN STREET	Drawing Number	Issue
ND HILL RS TOWERS	CBD0072/03	P2

Confirm size, location & elevation of all existing services on site before construction commences. Advise NORTHERN CONSULTING ENGINEERS of any discrepancies between dervices & cites













PAVEMENT DESIGN	
	Slab thickness – 150mm Reinforcing – SL82 mesh Cover – 40mm top cover Concrete – N32 Finish – To clients requirements Slab to be poured over 50mm fine gravel crusher dust or fine gravel deco. Subgrade proof roll with engineer required prior to placement of concrete.
	Slab thickness – 100mm Reinforcing – SL72 mesh Cover – Central Concrete – N32 Finish – To clients requirements Slab to be poured over 50mm fine gravel crusher dust or fine gravel deco.

----- - Existing RP boundary.





ISSUED FOR APPROVAL.		31/03/2023
Description		Date
	SITE BASED STORMWATER MANAGEMENT LAYOUT PLAN	
VELOPMENT KIN STREET D HILL RS TOWERS	Drawing Number	Issue
	CBD0072/SBSM01	P1

Confirm size, location & elevation of all existing services on site before construction commences. Advise NORTHERN CONSULTING

ENGINEERS of any discrepancies between drawings & site.

7. A conservative MUSIC model was prepared to confirm the treatment effectiveness whereby a lump sum residential pollutant source that represents the entire site was passed through a buffer and swale of 20m in length. The results of this assessment are shown on this drawing.

EROSION & SEDIMENT CONTROL:

 Existing sewer main. STORMWATER:

- Drainage path Invert.

------ - Existing RP boundary.

FLOODING

- In accordance with the DNRM flood hazard mapping bundle 1 Charters Towers and Millchester, the site is generally free from flooding and where flooding does occur it is a result of overland sheet flow, i.e. 1. 20_40mm
- 2. As the site is generally free from flooding, the finished floor levels (FFL) have been set in accordance with the NCC.


RUN-OFF QUANTITY

- Under existing conditions, the site discharged into the adjoining properties, therefore to comply with QUDM, earthworks is required to fall the site to the lawful point of discharge (LPOD), namely Baker Street.
- 4. The site had three (3) overland flow control points in which the predicted flow parameters for the 1% AEP. 5-minute even have been provided. Mannings equation has been used to define these parameters. This demonstrates that the run-off from the site can be conveyed overland to the LPOD without impacting the FFL of the building.

RUN-OFF QUALITY

- In accordance with the SPP, the site is classified as low risk and therefore best practices have been adopted.
- A shallow grassed swale is proposed through the central open space area and the rear of each unit will be grassed as well. These spaced will act as a swale to treat run-off.

- Buring construction, the contractor will be responsible for the development and implementation of soil erosion & sediment control measures in accordance with the TCC Development Manual SC6.4.3.8.6. Conceptually, devices such as sediment fences are anticipated at boundaries during earthworks.
- 9. At the completion or works, it is recommended that all disturbed areas are reinstated to existing conditions or better, i.e. turf or hydro-mulch.





- Finished surface fall direction. - Existing surface fall direction.

- Existing major contour. - Existing minor contour. - Existing major contour. - Existing minor contour.